

BIM Implementation and Management Processes in Public Tenders – A Subway Project in İstanbul



Emay International Engineering and Consultancy Inc.

PRESENTATION MAP

- ► **EMAY** International Engineering and Consultancy Inc.
- ► Istanbul Metropolitan Municipality (**IMM**)
- ► Istanbul Rail System
 - IMM Metro Projects
 - BIM Integration Process
- ► Kabataş–Mecidiyeköy–Mahmutbey Metro Line (**KMM**)
 - Project Management Portal - **PMP**
- ► BIM Methodologies Used in KMM
 - Pre-Construction Phase
 - Construction Phase
 - Post-Construction Phase
- ► Experienced Difficulties
- ► Conclusion
- ► Comparison



A. Sinan ALEMDAR

Deputy General Manager
Head of PMCM Group

Description Of Duties (Ongoing Projects)

- General Manager of Consultancy Works
- Director of 'Ataköy – İkitelli Metro' Project
- Director of 'Mecidiyekoy - Mahmutbey Metro' Project



International Engineering and Consultancy Inc.

Tel. +90 216 400 0 400

salemdar@emay.com

www.emay.com

Work Experience

- Emay International Engineering and Consultancy Inc. 1998 - Ongoing
- General Directorate of Highways, 17th Division Directorate 1994 – 1998

Education

- Istanbul Technical University, Civil Engineering (MSc) 1992 – 1996
- Istanbul Technical University, Civil Engineering (BSc) 1988 – 1992

Main Areas Of Expertise

- Project Management
- Railway Project
- Bridge Design
- Bridge/Geotechnical
- Tunnel Design



FIELDS OF ACTIVITIES AND SERVICES



Services

- ▼ Project Management
- ▼ Feasibility Study
- ▼ Architectural and Engineering Design /Geodetic Studies
- ▼ Transportation/Traffic Planning and Design
- ▼ Due diligence, Inspection, Analysis and Evaluation



Istanbul Metropolitan Municipality's responsibility includes an area of 5.343 km² with a length of
165 km East -> West direction
45 km North -> South direction




TRANSPORTATION SYSTEMS INVESTMENT



IN LAST 11 YEARS, Istanbul Metropolitan
Municipality SPENT

10,3 BILLION €

2016 ISTANBUL TRANSPORTATION DATA



15

MILLION
POPULATION




30

MILLION
DAILY TRIPS



520

NEW VEHICLES
ADDED TO
TRAFFIC/DAY



1.7

MILLION TRIPS
BETWEEN TWO
CONTINENTS

2016 ISTANBUL TRANSPORTATION DATA



3.62

MILLION
REGISTERED
VEHICLES



2.46

MILLION
VEHICLES IN
TRAFFIC/DAY



30.000

KM
TOTAL ROAD
NETWORK



45

MINUTES
AVERAGE TRAVEL
TIME /DAY




168

CAR OWNERSHIP
/ 1000 PERSON

Daily travelers and personal vehicles cause traffic congestion largely on highways

COMPARISON OF METROPOLITANS


İSTANBUL	LONDON
Rail System Length: 145,00 km	Rail System Length: 402,00 km
# of Bus: 6.317	# of Bus: 8.500
# of Taxi: 17.395	# of Taxi: 21.500
Population: 14.657.434	Population: 13,880,000
# of Car Per 1000 Person: 168	# of Car Per 1000 Person: 591
NEW YORK	PARIS
Rail System Length: 369,00 km	Rail System Length: 386,00 km
# of Bus: 4.373	# of Bus: 4.490
# of Taxi: 13.437	# of Taxi: 14.900
Population: 8.491.079	Population: 12,400,000
# of Car Per 1000 Person: 444	# of Car Per 1000 Person: 560



ISTANBUL METROPOLITAN CITY



RAILWAY NETWORK IN ISTANBUL – 2040 EXISTING – ONGOING - PLANNED




ISTANBUL RAIL SYSTEM

İSTANBUL RAIL LINE SYSTEMS IN 2019

NO	SITUTATION OF THE METRO LINE	KM
1	EXISTING METRO LINES	145,45
2	ONGOING METRO LINE CONSTRUCTIONS	156,20
3	METRO LINES PLANNED TO BE CONSTRUCTED BY 2019	148,55
	TOTAL	450,78

PUBLIC TRANSPORTATION DATA



IMM AIMS TO
 RAISE THE
 TRANSPORTATION
 RATE
 48.1%
 IN 2023

BIM MOTIVATION

Global competitiveness for the future projects

Innovative role in the construction sector in Turkey

Analyzing and preventing **additional costs** and **extension of project duration**

Ensuring that **work schedule** is followed

Detailed controlling of construction and finishing works and installation of MEP systems

Controlling sketches and shop drawings according to the advanced technical and economical procedures and Turkish and International Standards on time.




EMAY INVOLVES IN





IMM METRO PROJECTS

IMM ORGANISATION CHART



IMM RAIL SYSTEM PROJETS LIFE CYCLE



IMM METRO PROJECTS

TIMELINE OF BIM INTEGRATION IN IMM METRO PROJECTS

First phase of **KMM**

Jan 14

2014

2012

2013


- ▶ **EMAY** developed PMP System
Feb 12



BIM definition has been added in **RAIL SYSTEM** tenderings

Nov 13

- ▶ **EMAY** use M-Files in **KMM**
Jan 14



- ▶ **KMM** First 3D models of the stations
Jun 14



- ▶ **RAIL SYSTEM BIM** Specifications are added to the construction tender documents
Dec 14

TIMELINE OF BIM INTEGRATION IN IMM METRO PROJECTS

Second phase of **KMM**

May 15

NOW


BIM GOALS

2015

2016

2017

- ▶ **KMM BIM Execution Plan is prepared**
Sep 15



- ▶ **RAIL SYSTEM**
Integration of BIM in both Design & Construction tenders
Jan 16
- ▶ **KMM M-Files** is being used with stakeholders
Sep 16
- ▶ **RAIL SYSTEM Updated BIM specifications**
Aug 16

Oct 16

- ▶ **KMM 4D – 5D** BIM integration
- ▶ **KMM Operation and Maintenance**
- ▶ **KMM Interdisciplinary meetings on 3D models.**




HOW DOES A BIM INTEGRATED METRO PROJECT LOOK LIKE?

IMPORTANCE OF THE METRO LINE

BIM has been added in a Rail System construction works contract for the first time in Turkey.

Project Cost: Total
Alignment Length:




PROJ
KM: 5
DANUBIUS
2000
tas

KABATAS – MECIDIYEKÖY MAHMUTBEY (KMM)


Technical Information

- 2 stations on viaducts
- 2 cut and cover stations
- 12 tunnel stations
- 3 top-down stations
- 19 stations in total




COORDINATION AND COLLABORATION


Project Organization




Executive Dashboard



SOFTWARE SYSTEM





PRE-CONSTRUCTION PHASE

BIM METHODOLOGIES IN KMM

Contractual arrangements / necessary documentation

Document Coding System

proje	alt sistem	aşama	dili	doküman tipi
M7 0 00	000 00 00	0	0	0
M7 G 00	101 00 A1	0	T	1 A
M7 S 00	102 01 00(AR)	0	E	1 B
M7 S 01	103 02 01(CW)	3	M	1 C
	. 03 02(PS)	04	U	2 D
	. 04 03(SG)	05	A	2 .
	. 04(TL)	06		3 .
	05(EC)	07		3 .
	06(AX)	08		4 .
	ALT SİSTEM	09		4 .
	A1 ORTAK KOŞULLAR	10		. .
		11		. .
		12		. .
		13		. .
		14		. .
		15		. .
		16		. .
		17		. .
		18		. .
		19		. .
		20		. .

BIM Execution Plan

T.C. İSTANBUL BÜYÜKŞEHİR BELEDİYESİ
RAYLI SİSTEM DAİRE BAŞKANLIĞI
AVRUPA YAKASI RAYLI SİSTEM MÜDÜRLÜĞÜ

Kontrol Mühendisi / Control Engineer: Mustafa MURTEZA
 Kontrol Amiri / Control Chief: Mustafa MURTEZA
 Müdür Yardımcısı / Deputy Manager: Hasan PEZİK
 Müdür / Manager: Hasan PEZİK

İşin Adı / Name of the Work: KABAŞ-MECİDİYEKÖY-MAHMUTBEY METRO HATTI

Onay / Approved: / Şartlı Onay / Conditionally Approved: / Reddedildi / Rejected: / Bilgi İçin Alındı / For Information:

Model Check Lists

İSTANBUL BÜYÜKŞEHİR BELEDİYESİ

ŞİHİN ADI: _____
 İSTASYON ADI: _____

emay
 E M A Y ULUSLARARASI MÜHENDİSLİK ve MÜŞAVİRLİK A.Ş.

LOD Matrices

Item Category - Sıhhi Tesisat (Plumbing)	Model Definition	Information Category	Açıklama	Kabul/Var Evet/Yı	Red/Yok Hayır/Kötü	Notlar
Description: A 2D and 3D element.						
			uygun mu			
			apılmış mı			
			çuk mü			
			iş kümeleri korunmuşmu (Detach from			
			cut mu			
			apılmış mı			
			alitesi			
			alitesi			

Model Check Lists

İşin Adı / Name of the Work: KABAŞ-MECİDİYEKÖY-MAHMUTBEY METRO HATTI

EMAY ULUSLARARASI MÜHENDİSLİK ve MÜŞAVİRLİK A.Ş.

Proje Müdürü / Project Manager: A. Sinan ALEMDAR


Bilgi İçin Alındı / For Information:

Onay / Approved By: İsmail EROĞLU

Standartları	
Rahatlığı ve Güvenlik Programı	
Altyapı Tesisleri	
Uygunluk	
Ekki	
Manyetik Uyum Ve Kalite Güvencesi	
ir	
Döşeme	
avaları Kablo Merdivenleri ve Montajı	
öruları ve Döşenmesi	
Motorları	
Kontrol / Yol Verici Panoları	
r	
al Panoları veya Blokları	
lar ve Bağlantıları	
Göstergeler ve Ölçü Aletleri	
ge Lambaları	
Kesitli Kablolar ve Bağlantıları	
izleme	
İşlemleri	
er ve Numara Plakaları	
lar, Cıvatalar ve Diğer Tespit Malzemesi	
ian Temini	
ın Şaftları	
ği ve Güvenliği (İSG) & Sistem Emniyeti	
önetimi	

PRE-CONSTRUCTION PHASE


Architectural and Statical Models



By design subcontractors

PRE-CONSTRUCTION PHASE


Architectural And MEP Coordinated Models



Coordination between various disciplines (architectural, structural, MEP, etc.) have been easier.

C(1)-8 : 01 FFL PERON KAT (5)


PRE-CONSTRUCTION PHASE Examples From Station Models






PRE-CONSTRUCTION PHASE

Examples From Station Models

BIM models made it possible to assess all these parameters.




PRE-CONSTRUCTION PHASE
Examples From Station Models



PRE-CONSTRUCTION PHASE

All 2D CAD worksheets are exported from 3D Tunnel/Station models.




KMM CONSTRUCTION PHASE



CONSTRUCTION PHASE

Site Management

PROJECT MANAGEMENT



SITE SUMMARY

İlerleme

- 1- Sahada 2 aynada NATM Tünel kazısı çalışma yapıldı. 6.40 m ilerleme sağlandı. (Kalan NATM Tüneli : 1622.11 m)(18.09.2016)
- 2- Sahada 2 noktada TBM Tünel kazısı çalışma yapıldı. 32.20 m ilerleme sağlandı. (Kalan TBM Tüneli : 5893.93 m)(18.09.2016)
- 3- Sahada 2 aynada NATM Tünel kazısı çalışma yapıldı. 0.80 m ilerleme sağlandı. (Kalan NATM Tüneli : 1628.51 m)(17.09.2016)
- 4- Sahada 2 noktada TBM Tünel kazısı çalışma yapıldı. 26.60 m ilerleme sağlandı. (Kalan TBM Tüneli : 5926.13 m)(17.09.2016)
- 5- Sahada 1 noktada TBM Tünel kazısı çalışma yapıldı. 14.00 m ilerleme sağlandı. (Kalan TBM Tüneli : 5952.73 m)(16.09.2016)
- 6- Sahada 4 aynada NATM Tünel kazısı çalışma yapıldı. 1.60 m ilerleme sağlandı. (Kalan NATM Tüneli : 1629.31 m)(16.09.2016)

	Alan / Açıklama	Alt Alan / Dosya Adı	Seviye	Yükleyen Birim	Dosya
8.2016	S04 Mecidiyeköy İstasyonu Doğu Konkors	CT1 Aç-Kapa 1. Kısım GenelGorunum(2).jpg		İstasyon Kontrol Şefliği Kayıt :Ömer Kurşun Güncelleme :Ömer Kurşun	
8.2016	S04 Mecidiyeköy İstasyonu Doğu Konkors	CT1 Aç-Kapa 1. Kısım GenelGorunum.jpg		İstasyon Kontrol Şefliği Kayıt :Ömer Kurşun Güncelleme :Ömer Kurşun	
8.2016	S18 Mahmutbey İstasyonu E blok +6.95 kotu kazısı	TD2 Top Down 2. Kısım IMG_6938.jpg		İstasyon Kontrol Şefliği Kayıt :Muhammet Erk Güncelleme :Muhammet Erk	
8.2016	S18 Mahmutbey İstasyonu E blok +6.95 kotu kazısı	TD2 Top Down 2. Kısım IMG_6937.jpg		İstasyon Kontrol Şefliği Kayıt :Muhammet Erk Güncelleme :Muhammet Erk	
8.2016	S18 Mahmutbey İstasyonu C blok temel pc102 perdesi	TD1 Top Down 1. Kısım IMG_6919.jpg		İstasyon Kontrol Şefliği Kayıt :Muhammet Erk Güncelleme :Muhammet Erk	
8.2016	S18 Mahmutbey İstasyonu B blok temel pa102 perdesi	TD1 Top Down 1. Kısım IMG_6921.jpg		İstasyon Kontrol Şefliği Kayıt :Muhammet Erk Güncelleme :Muhammet Erk	
8.2016	S18 Mahmutbey İstasyonu A blok TEMEL PA101	TD1 Top Down 1. Kısım IMG_6924.jpg		İstasyon Kontrol Şefliği Kayıt :Muhammet Erk Güncelleme :Muhammet Erk	
8.2016	S18 Mahmutbey İstasyonu A BLOK TEMEL PA102	TD1 Top Down 1. Kısım IMG_6922.jpg		İstasyon Kontrol Şefliği Kayıt :Muhammet Erk Güncelleme :Muhammet Erk	

CONSTRUCTION PHASE

Activity Planing and Progress Track - PMP

- Activities are identified on system and Planned work schedule of the contractor is uploaded into the system

Activities

Tünel İmalat Forman Listesi													
Sıra	İmalat Sınıfı	Eleman No	Türü	Başlama	Bitiş	KM Başlangıç	KM Bitiş	Ring Başlangıç	Ring Bitiş	Proje Değeri / Gerç. Değer	TBM Araç		+
4	Çağlayan İstasyonu Peron Bağlantı Tüneli Kaplama Beton İmalatı B1 GKK.M7.S05.B1T.01/0.01/0 2/1/1/0	115inv	NATM KAPLAMA	P: 29.09.2016 G: 02.08.2016	P: 21.10.2016 G:	0,00	29,00			29,00 29,00 7,00			+ ✎ ✖
5	Kazım Karabekir İstasyonu Peron Bağlantı Tüneli Kaplama Beton İmalatı	702k mr	NATM KAPLAMA	P: 27.05.2016 G:	P: 27.12.2016 G:	0,00	13,00			13,00 13,00 0,00			+ ✎ ✖

Planned work schedule dates

- Actual work progress is uploaded based on the data from the site

Date





Tünel İlerleme Bilgileri													
Sıra	Tarih	Üretim Bileşen	İşletme Noktası	Ayına Başlangıç KM	Ayına Bitiş KM	İlerleme	Vardiya	Mühendis	UR	Form No	Dosya		+
5	05.03.2016	A - A2	Alibeyköy Batı Portalı	11003,10	11006,70	3,60		Gökhan Çelik	✓				+ ✎ ✖

Mevcut kayıtlar açıldı.

Tunnel start finish km values

CONSTRUCTION PHASE

NATM & TBM Tunnel Daily Track Graph - PMP



CONSTRUCTION PHASE

NATM Report - PMP



Tarih : 17/09/2016 (NATM)

Tünel Türü	Genelleştirilmiş Elemen No	Alan	Alan Açıklaması	Sıra	İnşaat Tanımı	İnşaat Sınıfı	KM Başlangıç (a)	KM Bitiş (b)	Proje Degeri (c)-(d-a)	Aynalı İlerleme (d)	Ustaları		Alçıları		Gereklenen İlerleme (f) = (e*0.8+g*0.2)	Kalan (h) = e-d	Planlanan		Gerçekleşen		Ortalama Hız (m)/gün (h-k)/(l-k)	Gerçekleşen Ortalama Hız (p) = J/(Tarih-N)	Mevcut İhtiyaç Kalan İhtiyaçın Tamamına Zamana İyri (c)-(p)*(l-Tarih)	Planlanan Tarihte Etilirilemesi için Gerekten Ortalama Hız (q) = (c)-(q)/(l-Tarih)	Bugün İhtiyaç İle		Geçmiş (r) = (r-r)	Tayaron	Tünel Tipi	Durum	Geometri Tipi	
											Kazı (e)	İsa (f)	Kazı (g)	İsa (h)			Başlangıç (k)	Bitiş (l)	Başlangıç (m)	Bitiş (n)					Gerçekleşen İlerleme (q)	Planlanan İlerleme (r)						
NATM	GKK.L04.ATO.H1 (Natr)	L04	Fulya - Mecidiyeköy Kesimi	1	Fulya - Mecidiyeköy Kesimi Anahat Tüneli (A Tipi) NATM Kazı Yapılması	GKK.M7.L04.ATO.01.14/1/00	5330,85	5403,59	72,74	73,3	73,3	65	73,3	0	73,3	28/10/2014	31/03/2015	0,47	28/10/2014	20/03/2015	0,51	19/03/2015		73,3	72,74		ESA İNŞAAT TAHHÜT. TIC. ŞTİ	NATM	Tamamlandı	A Tipi		
	GKK.L04.ATO.H2 (Natr)	L04	Fulya - Mecidiyeköy Kesimi	2	Fulya - Mecidiyeköy Kesimi Anahat Tüneli (A Tipi) NATM Kazı Yapılması	GKK.M7.L04.ATO.01.14/1/00	5272,59	5345,33	72,74	73,28	73,28	75	73,28	0	73,28	09/01/2015	31/03/2015	0,90	09/01/2015	06/04/2015	0,84	05/04/2015		73,28	72,74		5 ESA İNŞAAT TAHHÜT. TIC. ŞTİ	NATM	Tamamlandı	A Tipi		
	GKK.L04.BIT.101 (Natr)	L04	Fulya - Mecidiyeköy Kesimi	3	Fulya - Mecidiyeköy İstasyonları Arası Kesim Yaklaşım Tüneli NATM Kazı Yapılması	GKK.M7.L04.B1P.01.14/1/00	0	8,02	8,02	8,02	8,02	10	0	0	6,42					27/10/2015				6,42				ZORGUN İNŞAAT TAHHÜT. TIC. LTD. ŞTİ	NATM	Devam Ediyor	P Tipi	
	GKK.L04.BIT.102 (Natr)	L04	Fulya - Mecidiyeköy Kesimi	4	Fulya - Mecidiyeköy İstasyonları Arası Kesim Yaklaşım Tüneli NATM Kazı Yapılması	GKK.M7.L04.B1P.01.14/1/00	0	7,52	7,52	8,02	8,02	10	0	0	6,42					27/10/2015				6,42				ZORGUN İNŞAAT TAHHÜT. TIC. LTD. ŞTİ	NATM	Devam Ediyor	P Tipi	
	GKK.L04.IS1.01 (Natr)	L04	Fulya - Mecidiyeköy Kesimi	5	Darphanne - Mecidiyeköy Kesimi Kuyruk Hattı NATM Tüneli Yaklaşım Şaftı Kazı Yapılması	GKK.M7.L04.IS1.01.02/1/1/0	0	43,43	43,43	43,43	43,43	0	0	0	34,74	15/04/2015	13/07/2015	0,49	25/08/2015					34,74	43,43		529	ZORGUN İNŞAAT TAHHÜT. TIC. LTD. ŞTİ	NATM	Devam Ediyor	12x9 m Elips Şaft	
	GKK.L04.TT0.H1 (Natr)	L04	Fulya - Mecidiyeköy Kesimi	6	Fulya - Mecidiyeköy Arası Kesimi Anahat Tüneli (T Tipi) NATM Kazı Yapılması	GKK.M7.L04.TT0.01.14/1/00	5278	5330,85	52,85	52,5	52,5	66	52,5	66	52,5	0,35	02/05/2015	29/08/2015	0,44	03/05/2015	24/08/2016	0,11	27/08/2016		52,5	52,85		364	Gülermak Ağır San. İnş. Taah. A. Ş.	NATM	Tamamlandı	A Tipi
	GKK.L04.TT0.H2 (Natr)	L04	Fulya - Mecidiyeköy Kesimi	7	Fulya - Mecidiyeköy Arası Kesimi Anahat Tüneli (T Tipi) NATM Kazı Yapılması	GKK.M7.L04.TT0.01.14/1/00	5219,74	5272,59	52,85	36	36	40	0	0	28,8	16,85	01/06/2015	25/02/2016	0,20	25/05/2015				24/10/2017	28,8	52,85		606	Gülermak Ağır San. İnş. Taah. A. Ş.	NATM	Devam Ediyor	T Tipi
	GKK.L05.ATO.H1a (Natr)	L05	Mecidiyeköy - Çağlayan Kesimi	8	Mecidiyeköy - Çağlayan Kesimi Anahat Tüneli (A Tipi) NATM Kazı Yapılması	GKK.M7.L05.ATO.01.14/1/00	5632,05	5892,91	260,86	260,86	260,86	251	260,86	65	260,86	01/04/2015	23/02/2016	0,80	30/03/2015	25/03/2016	0,72	25/03/2016		260,86	260,86		30	ESA İNŞAAT TAHHÜT. TIC. ŞTİ	NATM	Tamamlandı	A Tipi	
	GKK.L05.ATO.H1b (Natr)	L05	Mecidiyeköy - Çağlayan Kesimi	9	Mecidiyeköy - Çağlayan Kesimi Anahat Tüneli (A Tipi) NATM Kazı Yapılması	GKK.M7.L05.ATO.01.14/1/00	6167,92	6874,88	706,96	694,61	694,61	662,6	684,39	8	692,57	12,35	17/11/2014	13/04/2016	1,38	18/11/2014	1,04	01/10/2016		692,57	706,96		170	ESA İNŞAAT TAHHÜT. TIC. ŞTİ	NATM	Devam Ediyor	A Tipi	
	GKK.L05.ATO.H2a (Natr)	L05	Mecidiyeköy - Çağlayan Kesimi	10	Mecidiyeköy - Çağlayan Kesimi Anahat Tüneli (A Tipi) NATM Kazı Yapılması	GKK.M7.L05.ATO.01.14/1/00	5597,45	5834,91	237,46	238,21	238,21	241	227,51	79	236,07	25/03/2015	11/02/2016	0,74	30/03/2015	1,44	20/09/2016		1,44	20/09/2016		222	ESA İNŞAAT TAHHÜT. TIC. ŞTİ	NATM	Devam Ediyor	A Tipi		
	GKK.L05.ATO.H2b (Natr)	L05	Mecidiyeköy - Çağlayan Kesimi	11	Mecidiyeköy - Çağlayan Kesimi Anahat Tüneli (A Tipi) NATM Kazı Yapılması	GKK.M7.L05.ATO.01.14/1/00	6109,29	6831,37	722,08	714,89	714,89	657	692,68	14	708,05	10,19	22/11/2014	29/02/2016	1,56	22/11/2014	1,06	30/09/2016		708,05	722,08		214	ESA İNŞAAT TAHHÜT. TIC. ŞTİ	NATM	Devam Ediyor	A Tipi	
	GKK.L05.BIT.401 (Natr)	L05	Mecidiyeköy - Çağlayan Kesimi	12	Mecidiyeköy - Çağlayan İstasyonları Arası Kesim Makas Yaklaşım Tüneli NATM Kazı Yapılması	GKK.M7.L05.B1P.01.14/1/00	0	18,26	18,26	18,26	18,26	18	4,2	0	15,45	20/08/2015	21/11/2015	0,29	29/08/2015	0,04	26/11/2016		15,45	18,26		371	SARGIN İNŞ. MAK. SAN. TIC. A. Ş.	NATM	Devam Ediyor	B1 Tipi		
	GKK.L05.CPN.01 (Natr)	L05	Mecidiyeköy - Çağlayan Kesimi	13	Mecidiyeköy - Çağlayan Kesimi Anahat Bağlantı Tüneli (B2 Tipi) NATM Kazı Yapılması	GKK.M7.L05.CPN.01.14/1/00	4,5	21,68	17,18	16,93	16,93	21	0	0	13,54	0,25	04/12/2014	13/12/2015	0,05	12/10/2014			26/03/2017	13,54	17,18		468	ESA İNŞAAT TAHHÜT. TIC. ŞTİ	NATM	Devam Ediyor	B1 Tipi	
	GKK.L05.CPN.02 (Natr)	L05	Mecidiyeköy - Çağlayan Kesimi	14	Mecidiyeköy - Çağlayan Kesimi Anahat Bağlantı Tüneli (B2 Tipi) NATM Kazı Yapılması	GKK.M7.L05.CPN.01.14/1/00	4,5	17,98	13,48	13,23	13,23	16	0	0	10,58	0,25	27/11/2014	08/12/2015	0,04	20/10/2014			27/03/2017	10,58	13,48		476	ESA İNŞAAT TAHHÜT. TIC. ŞTİ	NATM	Devam Ediyor	P Tipi	
	GKK.L05.CPN.03 (Natr)	L05	Mecidiyeköy - Çağlayan Kesimi	15	Mecidiyeköy - Çağlayan Kesimi Anahat Bağlantı Tüneli (B2 Tipi) NATM Kazı Yapılması	GKK.M7.L05.CPN.01.14/1/00	0	24,6	24,6	24,6	24,6	26	24,6	0	24,6	20/09/2015	21/11/2015	0,40	22/04/2016	09/05/2016	1,45	09/05/2016		24,6	24,6		170	Gülermak Ağır San. İnş. Taah. A. Ş.	NATM	Tamamlandı	A Tipi	
	GKK.L05.CPN.02 (Natr)	L05	Mecidiyeköy - Çağlayan Kesimi	16	Mecidiyeköy - Çağlayan Kesimi Anahat Bağlantı Tüneli (B2 Tipi) NATM Kazı Yapılması	GKK.M7.L05.CPN.01.14/1/00	0	7,56	7,56	7,56	7,56	9	7,56	0	7,56	20/09/2015	21/11/2015	0,12	19/11/2015	0,02	17/09/2016		7,56	7,56		300	SARGIN İNŞ. MAK. SAN. TIC. A. Ş.	NATM	Devam Ediyor	B1 Tipi		
	GKK.L05.CPN.03 (Natr)	L05	Mecidiyeköy - Çağlayan Kesimi	17	Mecidiyeköy - Çağlayan Kesimi Anahat Bağlantı Tüneli (B2 Tipi) NATM Kazı Yapılması	GKK.M7.L05.CPN.01.14/1/00	0	19,35	19,35	19,61	19,61	21	19,61	0	19,61	20/09/2015	21/11/2015	0,31	20/03/2015	12/08/2015	0,14	10/08/2015		19,61	19,35		120	ENTO MADENLİK İNŞ. SAN. TIC. LTD. ŞTİ	NATM	Tamamlandı	A Tipi	
	GKK.L05.CPN.04 (Natr)	L05	Mecidiyeköy - Çağlayan Kesimi	18	Mecidiyeköy - Çağlayan Kesimi Anahat Bağlantı Tüneli (B2 Tipi) NATM Kazı Yapılması	GKK.M7.L05.CPN.01.14/1/00	0	25,54	25,54	25	23	21,4	0	0	24,28	0,54	29/10/2015	24/06/2016	0,11	06/09/2015	0,06	07/10/2016		24,28	25,54		104	SARGIN İNŞ. MAK. SAN. TIC. A. Ş.	NATM	Devam Ediyor	A Tipi	
	GKK.L05.CTT.H0C (Natr)	L05	Mecidiyeköy - Çağlayan Kesimi	19	Mecidiyeköy - Çağlayan Kesimi Anahat Tüneli (C Tipi) NATM Kazı Yapılması	GKK.M7.L05.CTT.01.14/1/00	5933,17	6105,47	172,3	164,87	164,87	164	172,31	0	166,36	7,43	27/08/2015	06/03/2016	0,90	04/10/2015			0,48	29/09/2016	166,36	172,3		207	SARGIN İNŞ. MAK. SAN. TIC. A. Ş.	NATM	Devam Ediyor	C Tipi
	GKK.L05.IS1.01 (Natr)	L05	Mecidiyeköy - Çağlayan Kesimi	20	Mecidiyeköy - Çağlayan Kesimi NATM Şaftı Kazı Yapılması	GKK.M7.L05.IS1.01.02/1/1/0	0	54,94	54,94	54,94	54,94	0	0	0	43,95	03/05/2015	12/05/2015	6,10	27/04/2015	26/08/2015	0,25	25/09/2015		43,95	54,94		136	SARGIN İNŞ. MAK. SAN. TIC. A. Ş.	NATM	Tamamlandı	12x9 m Elips Şaft	
	GKK.L05.IS1.02 (Natr)	L05	Mecidiyeköy - Çağlayan Kesimi	21	Mecidiyeköy - Çağlayan Kesimi NATM Şaftı Kazı Yapılması	GKK.M7.L05.IS1.01.02/1/1/0	0	56,73	56,73	56,73	56,73	0	0	0	45,38	14/08/2014	12/12/2014	6,84	01/08/2014	11/11/2014	0,28	06/12/2014		45,38	56,73		136	ESA İNŞAAT TAHHÜT. TIC. ŞTİ	NATM	Tamamlandı	12x9 m Elips Şaft	
	GKK.L05.TT0.H0Ta (Natr)	L05	Mecidiyeköy - Çağlayan Kesimi	22	Mecidiyeköy - Çağlayan Arası Kesimi Anahat Tüneli (T Tipi) NATM Kazı Yapılması	GKK.M7.L05.TT0.01.14/1/00	5892,91	5933,17	40,26	40,26	40,26	41	40,26	0	40,26	17/07/2015	27/08/2015	0,98	26/11/2015	0,14	17/09/2016		40,26	40,26		387	SARGIN İNŞ. MAK. SAN. TIC. A. Ş.	NATM	Devam Ediyor	T Tipi		
	GKK.L05.TT0.H0Tb (Natr)	L05	Mecidiyeköy - Çağlayan Kesimi	23	Mecidiyeköy - Çağlayan Arası Kesimi Anahat Tüneli (T Tipi) NATM Kazı Yapılması	GKK.M7.L05.TT0.01.14/1/00	6105,47	6167,92	62,45	62,45	62,45	64	62,44	0	62,45	06/03/2016	13/05/2016	0,92	23/01/2016	0,26	17/09/2016		62,45	62,45		127	SARGIN İNŞ. MAK. SAN. TIC. A. Ş.	NATM	Devam Ediyor	T Tipi		
	GKK.L06.ATO.H1 (Natr)	L06	Çağlayan - Kağıthane Kesimi	24	Çağlayan - Kağıthane Arası Kesimi Anahat Tüneli (A Tipi) NATM Kazı Yapılması	GKK.M7.L06.ATO.01.14/1/00	7104,73	7660,08	555,35	554,78	554,78	564	488,40	40	541,58	0,57	08/08/2015	15/03/2016	2,52	13/06/2015	1,17	29/09/2016		541,58	555,35		197	ESA İNŞAAT TAHHÜT. TIC. ŞTİ	NATM	Devam Ediyor	A Tipi	
	GKK.L06.ATO.H2 (Natr)	L06	Çağlayan - Kağıthane Kesimi	25	Çağlayan - Kağıthane Arası Kesimi Anahat Tüneli (A Tipi) NATM Kazı Yapılması	GKK.M7.L06.ATO.01.14/1/00	7061,27	7628,28	567,01	565,8	565,8	567	253,46	62	503,33	1,21	15/08/2015	29/03/2016	2,50	15/08/2015	1,26	06/11/2016		503,33	567,01		222	ENTO MADENLİK İNŞ. SAN. TIC. LTD. ŞTİ	NATM	Devam Ediyor	A Tipi	
	GKK.L06.CPN.05 (Natr)	L06	Çağlayan - Kağıthane Kesimi	26	Çağlayan - Kağıthane Kesimi Anahat Bağlantı Tüneli (B2 Tipi) NATM Kazı Yapılması	GKK.M7.L06.CPN.01.14/1/00	0	24,6	24,6	12	12	14	3,6	0	10,32	12,6	29/10/2015	24/06/2016	0,10	24/07/2016	0,19	02/12/2016		10,32	24,6		161	ESA İNŞAAT TAHHÜT. TIC. ŞTİ	NATM	Devam Ediyor	A Tipi	
	GKK.L06.CPN.06 (Natr)	L06	Çağlayan - Kağıthane Kesimi	27	Çağlayan - Kağıthane Kesimi Anahat Bağlantı Tüneli (B2 Tipi) NATM Kazı Yapılması	GKK.M7.L06.CPN.01.14/1/00	0	8,8	8,8	7,54	7,54	10	0	0	6,03	1,26	29/10/2015	24/06/2016	0,04	20/04/2016			25/11/2016	6,03	8,8		153	ESA İNŞAAT TAHHÜT. TIC. ŞTİ	NATM	Devam Ediyor	A Tipi	
	GKK.L06.CPN.07 (Natr)	L06	Çağlayan - Kağıthane Kesimi	28	Çağlayan - Kağıthane Kesimi Anahat Bağlantı Tüneli (B2 Tipi) NATM Kazı Yapılması	GKK.M7.L06.CPN.01.14/1/00	0	3,92	3,92	0	0	0	0	0	3,92	29/10/2015	24/06/2016	0,02				0	3,92			0	ESA İNŞAAT TAHHÜT. TIC. ŞTİ	NATM	Başlamadı			
	GKK.L06.CTT.H0C (Natr)	L06	Çağlayan - Kağıthane Kesimi	29	Çağlayan - Kağıthane Arası Kesimi Anahat Tüneli (C Tipi) NATM Kazı Yapılması	GKK.M7.L06.CTT.01.14/1/00	7713,39	7803,72	90,33	90,38	90,38	230	89,58	115	90,22	13/01/2015	23/04/2015	0,90	11/01/2015	13/07/2015	0,49	13/07/2015		90,22	90,33		81	ESA İNŞAAT TAHHÜT. TIC. ŞTİ	NATM	Tamamlandı	C Tipi	
	GKK.L06.TT0.H0T (Natr)	L06	Çağlayan - Kağıthane Kesimi	30	Çağlayan - Kağıthane Arası Kesimi Anahat Tüneli (T Tipi) NATM Kazı Yapılması	GKK.M7.L																										


CONSTRUCTION PHASE

Daily TBM Report - PMP

MECİDİYEKÖY - MAHMUTBEY METRO İNŞAATI TBM TÜNELLER İLERLEME RAPORU




Gerçekleşen Ortalama Hız = 2.79 m/gün
 Son Hafta Gerçekleşen Ortalama Hız = 2.00 m/gün
 Son Ay Gerçekleşen Ortalama Hız = 3.04 m/gün



Gerçekleşen Ortalama Hız = 2.81 m/gün
 Son Hafta Gerçekleşen Ortalama Hız = 11.80 m/gün
 Son Ay Gerçekleşen Ortalama Hız = 2.02 m/gün

Toplam KM
2435,21


Hat-2 TBM Terratec / H2 tamamlanmıştır. 9,8 m ilerleme yapılmıştır. Döküm sahası ve Jeolojisi: Kil, Sil



Gerçekleşen Ortalama Hız = 7.22 m/gün

Son Hafta Gerçekleşen Ortalama Hız = 9.80 m/gün

Son Ay Gerçekleşen Ortalama Hız = 11.48 m/gün



CONSTRUCTION PHASE

Schedule & Budget Control - PMP

PROGRESS PAYMENT

815.655.436 TL

96%

Planned

558.664.458 TL

66%

Actual

PROJECT DURATION


953days 87,11%

To Date

141days 12,89%

Kalan Süre

Sıra	Aylar	Hakediş Kuru	Aylık Planlanan	Kümülatif Planlanan	Aylık Gerçekleşen	Kümülatif Gerçekleşen
1	Mart 14	TL	9,334,485.54	9,334,485.54		
2	Nisan 14	TL	17,139,829.30	26,474,314.84		
3	Mayıs 14	TL	19,656,162.19	46,130,477.03		
4	Haziran 14	TL	19,624,033.62	65,754,510.65		
5	Temmuz 14	TL	24,572,793.73	90,327,304.38	6,597,565.78	6,597,565.78
6	Ağustos 14	TL	30,909,159.25	121,236,463.63		6,597,565.78
7	Eylül 14	TL	32,905,299.87	154,141,763.50	5,578,111.78	12,173,677.54
8	Ekim 14	TL	32,305,710.83	186,447,474.33		12,173,677.54
9	Kasım 14	TL	29,703,060.27	216,150,534.60		12,173,677.54
10	Aralık 14	TL	38,806,502.18	254,957,036.78	38,551,065.96	48,724,743.50
11	Ocak 15	TL	42,681,738.80	297,638,775.58	49,212,972.80	68,039,617.10




CONSTRUCTION PHASE

Station Based Remote Data Input Track - PMP

Tarih	Birim Adı	Alan	Σ
12.08.2016	EM	S18 - Mahmutbey İstasyonu	2
12.08.2016	İstasyon	S04 - Mecidiyeköy İstasyonu	2
12.08.2016	İstasyon	S07 - Nurtepe İstasyonu	2
12.08.2016	İstasyon	S09 - Yeşilpınar İstasyonu	2
12.08.2016	İstasyon	S10 - Veysel Karani İstasyonu	2
12.08.2016	İstasyon	S12 - Kazım Karabekir İstasyonu	2
12.08.2016	İstasyon	S14 - Karadeniz Mahallesi	2
12.08.2016	İSG	G00 - TÜM GÜZERGAH	1
12.08.2016	Jeoteknik	G00 - TÜM GÜZERGAH	1
12.08.2016	NATM	L04 - Fulya - Mecidiyeköy Kesimi	1

Total: 17



Every responsible engineer inputs daily progress to the PMP system on his own.

CONSTRUCTION PHASE

Station Construction Is Underway

Finishing Works 3D Model View




Construction Site Existing Works




CONSTRUCTION PHASE

Finishing Works of 3D Model View





Alternate concept design models are prepared for Finishing Works



CONSTRUCTION PHASE

Render Models



CONSTRUCTION PHASE


Taking Data From Site To Office



CONSTRUCTION PHASE

Site Progress Track

BIM METHODOLOGIES IN KMM



The screenshot displays the Autodesk Navisworks Manage 2016 (STUDENT VERSION) interface. The main view shows a 3D model of a tunnel construction site with various phases highlighted in red and green. The interface includes a ribbon with tabs for Home, Viewpoint, Review, Animation, View, Output, BIM 360, and Render. A Selection Tree on the left lists various elements like Altyari, Ustyari, Kemer, Invert, Saft, 1.Asama, 2.Asama, and TamKesit. A Properties window on the left shows details for a selected element, including its name (YP_P1A_12m) and various attributes like Mark, ISTASYON ADI, TIPI, KISIM, KAT/ KOT, STRÜKTÜR, NO., ANO, TASARIMCI FIR., ÇİZEN, Phasing, and other properties. A Saved Viewpoints list on the right shows a hierarchy of views for the project, including dates and specific view names like S00-Genel Görünüm, S05-Mecidiyeköy, etc. The bottom status bar shows the current view is 'FRONT' and provides coordinates for a selected point: T1A(3066250)-TAA(4919229) : LEVEL Drenaj (127045) with X: 409875024 mm, Y: 4549894564 mm, Z: 123445 mm.

KMM POST-CONSTRUCTION PHASE




POST-CONSTRUCTION PHASE

BIM METHODOLOGIES IN KMM

- Consider Life – Cycle of subway
- Plan for next 100 years

- Add maintenance parameters to models and model family
- Integration of Models & Facility management software



CHALLENGES

- ▶ Changing business culture
- ▶ (Drawings 2D -> 3D)
- ▶ Users tend to use traditional methods for data sharing.
- ▶ Difficulties in preparation of BIM documents
- ▶ No BIM specification or regulation for horizontal construction works in Turkey.
- ▶ Lack of experienced subcontractors



During the project;

New station added to the line: The models were designed based on existing Document Coding System.

We had to number all the stations again. This caused approximately 1 month delay.




LESSONS LEARNED

- ▶ More detailing BEP document should be developed.
- ▶ The BEP document should include the Document Coding System which Emay developed.
- ▶ Procedures and work flows should be created. All the documents, even the minutes of meetings should be classified under a smart document system.
- ▶ All the stakeholders should be informed about BIM system and training must be mandatory via tender documents.



OUTLOOK

- ▶ Project owners should be involved to process.
- ▶ The implementation of BIM processes should be started immediately.
- ▶ Each project should create its own BIM process.
- ▶ Companies and Municipalities (owners) always have to seek for better solutions. Here, we try different CDE platforms in different projects.



OTOGAR – BAĞCILAR METRO PROJECT

STATUS	OTOGAR - BAĞCILAR	KABATAŞ - MAHMUTBEY
File tracking	Excel	M-Files
File archive method	Hard copy	Soft copy
Drawing tracking	Excel	M-Files
Drawing archive	Hard copy – Limited people	Soft copy - Everybody can Access (authorized)
OUTCOME	Last progress payment: June 2015 Now: 4 people still working for Final account	No delay on office works Expected
Additional Cost	6,200 Euro/month	

In traditional method;

Lack of document management system causes waste of time. You have to ask to related person to find a drawing file and this lowers the performance of people. We expect to finish office works as the site works finish.

IT WOULD ALL BE MUCH HARDER WITHOUT BIM!

COMPARISON TO A NON-BIM PROJECT



