

Laser Scanning / Coordination / 4D

at


Hoag Hospital, Newport Beach CA

Project - Who?

- VDC Services Team
- Hoag Healthcare
- Kemp Brothers General Contracting
- Subcontractors

Project - What?

Phased renovation of occupied emergency room, using scanning assist (for coordination) and 4D BIM (schedule planning and production control)



Laser Scan Coordination - Why?

- *MEPF systems crossing between phases*
- *Owner required transparency to inform hospital employees*
- *Mistakes in occupied spaces are \$\$\$*



5D BIM - Why?


- *Owner 'got' Flowline w/ production control*
- *Project schedule was slipping (badly)*
- *Owner did not feel in control*
- *Owner was having trouble communicating between contractors and staff*

Process – Scanning:

- *On-site kick-off meeting*
- *Scanning session 1, 2, 3*
 - *Scan plan*
 - *Photos / videos*
 - *Sketches*
- *Point clouds used as reference by modeling team*


Scan Plans





Video

Supporting Data






Process – Coordination:


- *Identify existing to remain work*
- *Identify points of connection*
- *Filter scans for above criteria*
- *Relate scan information with sketches, photos and videos from site*
- *Model creation: separation of ETR & New*


Coordination – Deliverables:

- *Composite Vico Office model*
- *Seven sub-models, per discipline*
- ***Constructability report (in Vico)***
- *2D installation drawings, per discipline*
- ***Photos, videos and sketches***

ID	INT-L-004	Trades Involved	A	Severity	Low
Description	Contradiction between scanned model and demolition first floor plan (A201.3). The position and the style of demolished walls are different on the scanned model, sketched drawing (3-reception room) and the demolition plan.				
Floor	First floor	Grid Reference	NJ-J1/8-N.08	Sheet Reference	A201.3
					

ID	MEP-K-004	Trades Involved	AP	Severity	Medium
Description	Clashes between 5 1/4" interior wall, 2" domestic hot water return pipe, 4" pneumatic tube pipe, and 2 1/2" domestic cold water pipe.				
Floor	First floor	Grid Reference	E5M-J/7-8	Sheet Reference	P211.3C; A211.3B
					
Modeling Assumption	DHWR was shifted to east with the distance of 1'-4 3/4", DCW pipe was shifted to west with the distance of 10" to avoid clashes.				






Process – 4D BIM:

- *Takeoff items broken down by: Project phase, element status, MEPF system*
- *Existing CPM activities put into Vico tasks*
- *Takeoff items linked to ‘cost plan’ items to quantify construction activities*
- *CPM match using quantity loaded tasks*
- *On-site review meetings*










Takeoff Manager New ViewSet(1)


Code	Description	Unit	Type	Value
	Quantity			
	B1012_025_CIP RC Wall			(0)
	B1012_001_Slab on Deck			(0)
	B1011_046_CIP RC Column			(0)
	CR			(2)
	(P5 NEW) C1011_Int Wall - NON RATED PART INSULATED			(70)
	Count	EA		70.00
	Length	FT-IN		699'-10 ...
	Reference Side Surface Area	SQ FT		10,547.73
	Opposite Reference Side Surface Area	SQ FT		10,369.00
	Top Surface Area	SQ FT		298.85
	Bottom Surface Area	SQ FT		271.22
	Ends Surface Area	SQ FT		829.49
	Reference Side Opening Surface Area	SQ FT		434.00
	Opposite Reference Side Opening Surface Area	SQ FT		434.00
	Net Volume	CU YD		687.38
	Gross Volume	CU YD		694.54
	(P5 NEW) C1011_Int Wall - 2-HR INSULATED			(3)
	(P5 NEW) C1011_Int Wall - 1-HR OCCUPANCY INSULATED			(11)
	(P4 NEW) C1011_Int Wall - NON RATED PART INSULATED			(152)
	(P4 NEW) C1011_Int Wall - 1-HR SMOKE RATED			(76)



3D View

Description	Type	Project	Elements w/...	Phase 3B	Phase 4	Phase 1	Phase 5
Quantity	Unit						
(P5 NEW) C1011_Int Wall - NON RAT...	(70)						
Count	EA	70.00	1.00	0.00	0.00	0.00	69.00
Length	FT-IN	699'-10 7/32"	0'	0'	0'	0'	699'-10 7/32"
Reference Side Surface Area	SQ FT	10,547.73	0.00	0.00	0.00	0.00	10,547.73
Opposite Reference Side Surface Area	SQ FT	10,369.00	0.00	0.00	0.00	0.00	10,369.00
Top Surface Area	SQ FT	298.85	0.00	0.00	0.00	0.00	298.85
Bottom Surface Area	SQ FT	271.22	0.00	0.00	0.00	0.00	271.22
Ends Surface Area	SQ FT	829.49	0.00	0.00	0.00	0.00	829.49
Reference Side Opening Surface Area	SQ FT	434.00	0.00	0.00	0.00	0.00	434.00
Opposite Reference Side Opening Surface Area	SQ FT	434.00	0.00	0.00	0.00	0.00	434.00
Net Volume	CU YD	687.38	0.00	0.00	0.00	0.00	687.38
Gross Volume	CU YD	694.54	0.00	0.00	0.00	0.00	694.54

Takeoff Manager




Process – Production Control:

- *Simulation presented to site team for validation of sequencing = revisions!*
- *CPM schedule durations, now quantity loaded, to site team for validation = revisions!*
- *Manpower loading of activities*
- *Production control roll-out*


Production Control - Deliverables:

- ***Vico Office*** file, with coordinated design, element quantities and 4D tasks
- ***Flowline*** printouts, by phase
- ***Gantt*** printouts, by phase
- ***Resource*** histograms, by trade
- ***Completion*** charts, by trade

Production Control - Deliverables:



Production Control - Deliverables:



Production Control - Deliverables:

2	3	Phase/Zon										
Floor 1	Phase 3B	TECH	9/29 9/30	10/4 10/4	10/5 10/5	10/6 10/6	10/6 10/6					
			9/29 9/29	10/4 10/5	10/6 10/6	10/6 10/6	10/6 10/6					
			9/27 9/29	9/29 10/4	10/4 10/6	10/6 10/6	10/6 10/6					
			9/27 9/28	9/30 10/1	10/6 10/6	10/4 10/6						
		RAD1	11/1 11/3	11/3 11/3	11/22 11/15	11/24 11/18	11/25					
								11/18 12/3				
								11/18 0/6				
		RAD3										
		RAD2	11/3 7/6	11/10 7/6	11/15 8/5	11/18 11/24						
			FRAME TEMP WALLS	DRYWALL & TAPE TEMP 1HR R WALLS	PAINT TEMP 1HR WALLS	ALL DEMO	INSTALL STRUCTURAL STEEL	PIPING SUPPORTS/UNISTRUT T GRID	*RF166 FIREPROOF REMOVAL	*STRUCTURAL UPGRADE E (SHEAR WALL)	*RF1044 AND FIX	*NORTH FOOTING

-3 PREFERRED CEILINGS					
CEILING GRID-1					
CEILING TILE-1					
PATCH CEILINGS AT TEMP 1HR WALLS					
-4 CRAFTSMAN CONCRETE CUTTING					
ALL DEMO		7	7	7	7
DEMO FIXTURES & ACCESSORIES					
-4A NEUBAUER ELECTRIC					
IDENTIFICATION OF EXISTING			2		
SAFE OFF		3	1	2	
CUTOVER SYSTEMS TO REMAIN ONLINE					
OVERHEAD ROUGH-IN					
PANEL INSTALLATION AND TERMINATIONS					
-5 CH STONE PLUMBING					

File

Scan / Coordination - Benefits:

- **3D Coordination**
 - *Recognized ETR, New and POC*
 - *Recognized phasing*
- **System Priority Structure driven coordination choices**
- **2D printouts for non-BIM installers**

4D / Production Control - Benefits:

- *Flowline is **visual** (increased buy-in)*
- *Installation **simulations** (subs & staff)*
- *Quantity loaded tasks = **reality check!***
- ***Clarity** on project status and risk*
- *Printouts for **non-BIM** installers*

Lessons Learned:

- ***Plan, Plan & Plan (scanning)***
 - *Have a **backup** plan!*
- ***Realistic and agreed upon expectations***
- ***Over communicate (VDC, GC, Subs, staff)***
- ***Identify and focus on priority elements***
- ***Small goals / milestones***
- ***Buy-in***

Thank You!!

duane_gleason@trimble.com

On: **Linked in**